

ஆனைகுட்டம் பஞ்சாயத்து ஆனைகுட்டம் அங்கன்வாடி புனரமைப்பு அளவீடுகள்

Sl.No.	Particulars	UOM	No. of unit	Meeter			Total	Rate	Amount
				L	B	D			
1	Old toilet demolition work floor	Cum		1.05	1	0.3	0.315		
2	Urinal Solid block work	Cum		3	0.15	0.9	0.405		
3	RR MASONRY FOUNDATION	Cum							
3	RCC for Roof slab	Cum		1.58	1.65	0.1	0.261		
	PCC for floor	Cum		1.05	1	0.1	0.105		
		Cum		1.2	1.05	0.1	0.126		
	Total	Cum					0.231		
4	Urinal Tiles work for 1) Walls	Sq.mt		3.2		1.2	3.840		
		Sq.mt		3.6		1.2	4.320		
	Total	Sq.mt					8.160		
	2) Floor	Sq.mt		1.05		1	1.050		
		Sq.mt		1.2		1.05	1.260		
	Total	Sq.mt					2.310		
5	Plastering walls ceilings	Sq.mt		1.2		1.05	1.26		
	inside wall	Sq.mt		3.6		0.9	3.24		
	outer wall	Sq.mt		4.05		1.15	4.66		
	roof screeding	Sq.mt		1.5		1.65	2.475		
	Total						11.63		
6	Painting for all wall and ceiling	Sq.mt		1.2		1.05	1.26		
		Sq.mt		1		1.05	1.05		
	inner wall	Sq.mt		3.2		2.1	6.72		
		Sq.mt		3.6		2.1	7.56		
	outer wall	Sq.mt		8.62		2.35	20.26		
		Sq.mt	2	0.9		2.1	3.78		
	Total	Sq.mt					33.07		
7	Joinery details 1)DOOR	Sq.mt	2	0.9		2.1	3.78		
8	Enamel Painting for Door (2x2side)	Sq.mt	4	0.9		2.1	7.56		
9	Oriyafan IWC	Nos	1				1		
10	wash basin	Nos	1				1		
11	Tap	LS	2				2		
12	Electrical work for Toilets 2 no's of tube light with wires and switches	LS					LS		
13	Sock pit 2 nos	Cum	2	1	1	1	2		
14	urinal Soak pit 1 no's	Cum	1	1	1	1	1		
15	Drainage pipe for 0.3mdia	RM	1	7			7		
16	500 litre water tank fixing	LS					LS		
	TOTAL								
II	Store Room								
1	Self work 4 rows	Sqmt	4	1.2	0.45		2.16		
2	Self work 1 row	Sqmt	1	3.2	0.6		1.92		
3	Jolly Pest net work	Sqmt	2	0.9	0.45		0.81		
4	Painting Walls	Sqmt		11.2	3		33.6		
	Deduction a)Doors 1No1	Sqmt	1	1	2		2		
	Total						31.6		
5	Enamel Painting 1) Door 1 No.	Sqmt	1	1	2		2		
	TOTAL								
III	Kitchen Room								
1	Demolish old tank	Cum	1	1	1	1	1		
2	Kitchen Sink	No	1				1		
3	Plasting Walls .06m height	Sq.ft		11.5	0.6		6.9		
4	Self work 4 rows	Sq.ft	4	1.2	0.45		2.16		
5	Jolly Pest net work	Sq.ft	1	1.9	0.45		0.86		
6	Electrical Work 2 Tube light switches & wire	LS					LS		
7	Painting Walls	Sq.ft		13.5	3		40.5		
	Deduction a)Doors 2 No	Sq.ft	2	1	2		4		
	b) Windows 1 No	Sq.ft	1	1	1		1		
	Total	Sq.ft					35.5		
8	Enamel Painting 1) Door 2 No.	Sq.ft	2	1	2		4		
	TOTAL								
II	Main building Hall								
1	Main New Door & Replacement Work	Sq.mt		1	2		2.00		
2	Jolly Pest net work	Sq.mt	6	2.4	1.6		23.04		

	3	Shelf work cuddapah slap 4 rows	Sq.mt	4	1.2	0.45		2.16	
	4	Demolish jolly	cum	7	2.4	0.04	0.9	0.60	
	5	Solid block work	Cum	7	2.4	0.1	0.9	1.51	
	6	Plastering 2 side	Sq.mt	14	2.4	0.9		30.24	
	7	Electrical work 2 Fans, 2 Tube Light Switches wire and fitting item main box cover	LS					LS	
	8	Painting work on wall	Sq.mt	1	34.7	3		104.1	
		Deduction a) Doors 2 Nos	Sq.mt	2	1	2		4	
		Total	Sq.mt					100.1	
	9	Enamel Painting 1) Door 2 No.	Sq.mt	2	1	2		4	
	10	Fals Ceiling by using thermocol	Sq.mt		12	6		72	
		TOTAL							
IV		Outerside							
	1	Remove Old Aspetaas sheet and fix new sheet	sq.mt		16.5	7.5		123.75	
	2	Aspetaas top force	cum		21.94	0.256	0.127	0.71	
	3	Pastering top force	sq.ft		21.94	0.425		9.32	
	4	Painting Work ouetr Wall	sq.mt	1	45	3.914		176.13	
		Deduction a) Doors 1 Nos	sq.mt	1	1	2		2	
		b) Windows 1 Nos	sq.mt	1	1	1.5		1.5	
		Total						172.63	
	5	Joinery Enamel Paint 1) Doors 2Nos 2 side	sq.mt	4	1	2		8	
		2) Window 1 Nos 2 side	sq.mt	2	1	1.5		3	
		Total	sq.mt					11	
		TOTAL							
		Micelaneous Expenses	LS					LS	
		Total							