

சிவகாசி மாநகராட்சி அண்ணாகாலனி அங்கன்வாடி(தாய் சேய் நலவிடுதி) புனரமைப்பு அளவீடுகள்

Sl.No.	Particulars	UOM	Meeter			Total	Rate	Amount
			Unit	L	B			
<b>TOILET &amp; URINAL</b>								
1	Old toilet demolition work wall& Floor	Cum		3.3	0.115	2.1	0.800	
	Foor	Cum		1.4	1.5	0.3	0.630	
	<b>Total</b>	Cum					<b>1.430</b>	
2	Earth work excavation	Cum		7.2	0.6	0.45	1.944	
3	RR Masonry Foundation	Cum		7.2	0.6	0.45	1.944	
4	RR Masonry Basement	Cum		7.2	0.45	0.45	1.458	
5	Basement Belt RCC 1:2:4	Cum		8.84	0.3	0.1	0.265	
6	Solid block for walls	Cum		8.55	0.15	2.1	2.693	
	<u>Deduction</u>							
	a) Door 2 Nos	Cum	2	0.9	0.15	2.1	0.567	
	b) Jolly 1 Nos	Cum	1	0.6	0.45	0.15	0.041	
	<b>Total</b>	Cum					<b>2.086</b>	
7	RCC for Roof slab	Cum		2.55	1.95	0.1	0.497	
8	PCC for flooring 2Nos	Cum	2	1.35	1.05	0.1	0.284	
9	Tiles work for 1) Walls	Sq.mt		9		1.2	10.8	
	<u>Deduction</u> Door 2 No (3 Side)	Sq.mt	3	0.9		1.2	3.240	
	<b>Total</b>	Sq.mt					<b>7.560</b>	
10	2) Floors	Sq.mt		1.35	1.2		1.62	
		Sq.mt		1.35	0.6		0.81	
	<b>Total</b>	Sq.mt					<b>2.43</b>	
11	Plastering walls <u>ceilings</u>	Sq.mt	1	1.35		1.8	2.43	
	inside wall	Sq.mt	1	5.1		2.1	10.71	
		Sq.mt	1	3.9		2.1	8.19	
	outer wall	Sq.mt	1	7.8		3.65	28.47	
	roof screeding	Sq.mt	1	2.25		1.65	3.71	
	<u>Deduction</u> Door 2 Nos (4Side)	Sq.mt	4	0.9		2.1	7.56	
	Jolly 1 Nos (2sides)	Sq.mt	2	0.6		0.45	0.54	
	<b>Total</b>	Sq.mt					<b>45.41</b>	
12	Painting same as Plastering area except roof screeding	Sq.mt					<b>41.70</b>	
13	Joinery details 1)DOOR	Sq.mt	2	0.9		2.1	3.78	
14	2)JOLLY	Sq.mt	1	0.6		0.45	0.27	
15	Enamel Painting for Door (1.5x2side)	Sq.mt	4	0.9		2.1	7.56	
16	Oriyafan IWC	Nos	2				2	
17	wash basin	Nos	1				1	
18	Tap	LS	2				2	
19	Electrical work for Toilets 2 no's of tube light with wires and switches	LS					LS	
20	Mesh work in jolly(SS)	Sq.mt	1	0.6		0.45	0.27	
21	Sock pit 2 nos	Cum	2	1	1	1	2	
22	urinal Soak pit 1 no's	Cum	1	1	1	1	1	
23	Drainage pipe for 0.3mdia	RM	1	7			7	

	24	500 litre water tank fixing	LS					LS	
								<b>Total</b>	
<b>II</b>		<b>Main building Hall</b>							
	1	Floor Tile Work	Sq.mt		6		5.9	35.40	
	2	Shelf work cuddapah slap 4 rows	Sq.mt		1.2	0.45	4	2.16	
	3	Painting work on wall & ceiling 1 coat white wash with 2 coat paint	Sq.mt						
		a) Ceilling	Sq.mt		6		5.9	35.40	
		b) Walls	Sq.mt		23.8		3	71.4	
		<u>Deduction</u> a) Doors 2Nos	Sq.mt	2	1		2.1	4.2	
		b) Windows 3Nos	Sq.mt	3	0.9		1.2	3.24	
		<b>Total</b>	Sq.mt					<b>99.36</b>	
	4	Enamel Paint 3 Windows	Sq.mt	3	0.9		1.2	3.24	
		Enamel Paint 1 Door	Sq.mt	1	1		2.1	2.1	
		<b>Total</b>	Sq.mt					5.34	
								<b>Total</b>	
<b>III</b>		<b>Kitchen</b>							
	1	Tile flooring	Sq.mt		2.9	2.65		7.685	
	2	Kitchen sink with cuddapah sab	set 1No						
	3	Painting work on wall & ceiling 1 coat white wash with 2 coat paint	Sq.mt						
		a) ceiling	sq.mt		2.9	2.65		7.685	
		b) Walls	sq.mt		11.1		3	33.3	
		Deductions							
		a) Door 2No	sq.mt	2	1		2.1	4.2	
		b) Windows 2 Nos	sq.mt	2	0.9		1.2	2.16	
		<b>Total</b>	Sq.mt					<b>34.63</b>	
	4	Enamel Paint 2 Windows	Sq.mt	2	1		1.2	2.4	
		Enamel Paint 1 Door	Sq.mt	1	1		2.1	2.1	
		<b>Total</b>	Sq.mt					4.5	
								<b>Total</b>	
<b>IV</b>		<b>Store room</b>							
	1	Tile work for Storeroom Floors	Sq.mt		3.05	2.9		8.84	
	2	Painting work 1 coat whitewash with 2 coat paint	Sq.mt						
		Ceiling	Sq.mt		3.05	2.9		8.84	
		Walls	Sq.mt		11.9		3	35.7	
		<u>Deductions</u> 1) Doors 1No	Sq.mt	1	1		2.1	2.1	
		2) Windows 1No	Sq.mt	1	0.9		1.2	1.08	
			Sq.mt					<b>41.36</b>	
	3	Enamel Paint 1) 1 Door	Sq.mt	1	1		2.1	2.1	
		2) 1 Windows	Sq.mt	1	1		1.2	1.2	
		<b>Total</b>						3.3	
								<b>Total</b>	
<b>V</b>		<b>Outer side</b>							
	1	Painting work on wall 1 coat white wash with 2 coat paint	sq.mt		32.1		4.65	149.265	
		<u>Deduction</u> a) Door 1 No	sq.mt	1	1		2.1	2.1	

		b) Windows 6No	sq.mt	6	0.9		1.2	6.48			
		<b>Total</b>	Sq.mt					140.685			
	2	Joinery enamel painting	sq.mt								
		a) Windows 6No	sq.mt	6	0.9		1.2	6.48			
		b) Door 1No	sq.mt	1	1		2.1	2.1			
		<b>Total</b>	Sq.mt					8.58			
		<b>Total</b>									
<b>VI</b>		<b>Miscellaneous Expenses</b>	<b>LS</b>					<b>LS</b>			
		<b>Total</b>									