

S.NO	Description of Work	Dimensions (Metre)			Total Qty	UNIT
		L	B	D		
<b>Toilet and Urinal</b>						
1	Earthwork Excavation	10.9	0.45	0.94	4.63	CUM
2	RR Masonry for Foundation	10.9	0.45	0.94	4.63	CUM
3	RR Masonry for Basement	10.9	0.45	0.47	2.31	CUM
4	Basement Belt RCC 1:1.5:3,6"TK	10.9	0.45	0.1	0.50	CUM
5	Gravel Filling in Basement	2.72	1.55	0.57	2.41	CUM
6	PCC 1:4:8 for Basement	2.49	1.3	0.15	0.48	CUM
7	B/W with CM 1:5	10.9	0.15	2.33	3.81	CUM
8	RCC Roof 1:2:4 , 6"tk	2.72	1.82	0.15	0.77	CUM
9	Plastering work with CM 1:3					
	inner	10		2.1	21.00	
	outer	10.9		2.44	26.60	
	ceiling	2.1	1.5		3.15	
	<u>Deduction</u>				1.47	
					48.68	SQM
10	1 coat Prime with 1 coat emulsion	as per plastering measurement			48.68	SQM
11	Doors Details a) Door	0.9		2.17	1.95	SQM
	b) Door1	0.9		1.03	0.93	SQM
12	Enamel Paint For Doors				2.88	SQM
13	DPC for on the Roof	2.3	1.36		3.14	SQM
14	Vetrified Tiles on wall	10		0.9	9.00	
	Floor	2.1	1.5		3.15	
	<u>Deduction</u>				1.38	
					10.77	SQM
15	Barbending and shuttering Belt	10.9	0.71		7.8	
	Roof	2.72	1.82		5	
					12.8	SQM
16	500 litre tank + Plumbing and IWC orisa pan, Soak pit-2No, 1/2 hp motor fixing and Wash Basin 1 set					LS
17	Sundrises					LS
<b>KITCHEN WORK</b>						
1	Floor Demolish,Tiles laid in kitchen	2.51	2.51		6.3	sqm
2	Cuddapahslab work by using B/W	1.52		1.71	2.6	sqm
3	Chimney Demolishing	2.44	0.23	1.52	0.85	cum
4	Kitchen slab Provided with sink	3.28	0.61		2	sqm
5	Scrap the old Painting and apply 2 coat Emulsion Wall	10.1		3.04	30.8	
	Ceiling	2.5	2.5		6.3	
	<u>Deduction</u>				3.98	
					33.12	sqm
<b>STORE ROOM WORK</b>						
1	Cuddapahslab work by using B/W	1.29		2.13	2.76	sqm
2	Floor Demolish,Tiles laid in Store	2.52	1.3		3.27	sqm

3	Scrap the old Painting and apply 2 coat Emulsion Wall	7.6		3.04	23.1	
	Ceiling	1.3	2.52		3.28	
	<u>Deduction</u>				1.78	
					24.6	sqm
<b>Hall work</b>						
1	Scrap the old Painting and apply 2 coat Emulsion wall	17.9		3.04	54.4	
	Ceiling	6	3		18	
					2	
					70.42	sqm
<b>Outerside work</b>						
1	DPC Repair work					LS
2	Scrap the old Painting and apply 2 coat Emulsion wall	27.5		5.4	148.2	sqm
3	Patches work on Ceiling and Base					LS
4	Enamel Paint For joinerys Door 3x2	0.93		2.1	11.7	sqm
<b>Compond wall</b>						
1	Earthwork Excavation	15.2	0.45	0.94	6.4	cum
2	RR Stones by using Foundation	15.2	0.45	0.94	6.4	cum
3	RR Masonry for Basement	15.2	0.45	0.3	2	cum
4	Basement Belt RCC 1:2:4 6"tk	15.2	0.45	0.15	1	cum
5	B/W by using CM 1:5	11.14	0.23	1.21	3.12	cum
6	Plastering on wall CM 1:3	30.4		1.67	50.7	sqm
7	1 coat Prime 1 coat emulsion	30.4		1.67	50.70	sqm
8	MS gate Provided	1.36		1.21	1.65	sqm
<b>MISCELLANEOUS WORK</b>						
1	Electrical and Plumbing work, Soak pit for Kitchen waste and Rainwater Harvesting					LS
2	Sundry					LS