

செங்கமலபட்டி அங்கன்வாடி புணரைமைப்பு அளவீடுகள்

Sl.No.	Particulars	UOM	Meeter				Rate	Amount
			unit	L	B	D		
I	TOILET & URINAL							
1	Toilet flooring demolish and work	Cum	1	1.8	1.9	0.1	0.35	
2	PCC work	Cum	1	1.8	1.9	0.1	0.35	
3	Tiles work for baby toilet 1) Floor	Sqmt	1	1.8	1.9		3.42	
4	Joinery details 1)DOOR repaire work	LS					LS	
5	Painting for 1) baby toilet Ceing	Sqmt	1	1.8	1.9		3.42	
	2) Teacher toilet Ceing	Sqmt	1	1.8	2		3.60	
	Total	Sqmt					7.02	
6	wash basin	Nos	1				1	
7	Tap	LS	1				LS	
8	Electrical work for Toilets 1 no's of tube light with wires and switches	LS					LS	
9	Mesh work in jolly(SS)	Sqmt	2	0.6		0.45	0.54	
10	Drainage pipe for 0.3mdia	RM	1	7			7	
	TOTAL							
II	Main building Hall							
1	selft work 4 rows	Sqmt	4	1.2	0.45		2.16	
2	0.60 m Remove old plastering	Sqmt	1	18.35		0.6	11.01	
3	0.60 m plastering	Sqmt	1	18.35		0.6	11.01	
4	Painting work on wall & ceiling 1 coat white wash with 2 coat paint 1) Ceiling	Sqmt	1	6	4		24.00	
	2) Wall	Sqmt	1	20		3	60.00	
	Deduction a)Windows 4Nos	Sqmt	4	1.2		1.2	5.76	
	b) Doors 2Nos	Sqmt	2	0.9		2.1	3.78	
	Total	Sqmt					74.46	
5	Window Repaire	LS					LS	
	TOTAL							
III	Kitchen							
1	Kitchen Sink set 1 No	LS					LS	
2	Kitchen Platform	Sqmt	1	1.2	0.6		0.72	
3	Tap	Nos	1				1	
4	Tile Flooring	Sqmt	1	3	1.9		5.70	
5	Electical Work 1 Tube light	LS					LS	
6	0.60 m Remove old plastering	Sqmt	1	7.8		0.6	4.68	
7	0.60 m plastering	Sqmt	1	7.8		0.6	4.68	
8	Painting work on wall & ceiling 1 coat white wash with 2 coat paint a) ceiling	Sqmt	1	3	1.9		5.70	
	b) Walls	Sqmt	1	9.8		3	29.40	
	Deductions a) Window 2No	Sqmt	2	1.2		1.2	2.88	
	b) Door 2No	Sqmt	2	1		2.1	4.20	
	Total						28.02	
	TOTAL							
IV	Store Room							
1	0.60 m Remove old plastering	Sqmt	1	9.2	0.6		5.52	
2	0.60 m plastering	Sqmt	1	9.2	0.6		5.52	
3	Foor Tiles	Sqmt	1	3	2.1		6.30	
4	Shelf work cuddapah slab 4 rows	Sqmt	4	2	0.45		3.60	
5	Shelf work cuddapah slab 1 rows	Sqmt	1	3	0.6		1.80	
6	Painting work on wall 1 coat white wash with 2 coat paint 1) Ceiling	Sqmt	1	3	2.1		6.30	
	2) Wall	Sqmt	1	10.2		3	30.60	
	Deduction a) Door 1No	Sqmt	1	1		2.1	2.10	
	Total						34.80	
	TOTAL							
V	Outerside							

