

**சிவகாசி மாநகராட்சி திருத்தங்கள் அங்கன்வாடி(செலிராயம்மன் கோவில் அருகில்) புனர்மைப்பு அளவீடுகள்**

Sl.No.	Particulars	UOM	Meeter				Total	Rate	Amount
			unit	L	B	D			
<b>I TOILET &amp; URINAL</b>									
1	Solid block for walls	Cum	1	1.8	0.15	2.1	0.570		
2	Plastering walls ceilings	Sq.mt	2	1.8		2.1	7.560		
3	Tiles work for 1) Floor	Sq.mt	2	1.8		1.5	5.400		
	2) Wall	Sq.mt	2	5.7		1.2	13.680		
4	Joinery details 1)DOOR	Sq.mt	2	0.9		2.1	3.780		
5	Painting for 1) Inside and Ceiling	Sq.mt		4.2	1.8		7.560		
	2) Walls	Sq.mt		12		2.1	25.200		
	3) Outside	Sq.mt		9.3		4.65	43.250		
	<b>Total</b>	Sq.mt					<b>76.01</b>		
6	Enamel Painting for Door (2side x 2Nos)	Sq.mt	4	0.9		2.1	7.56		
7	Oriyafan IWC	Nos	1				1		
8	wash basin	Nos	1				1		
9	Tap	LS	3				3		
10	Electrical work for Toilets 2 no's of tube light with wires and switches	LS					LS		
11	Mesh work in jolly(SS)	Sq.mt	3	0.6		0.45	0.81		
12	Drainage pipe for 0.3mdia	RM	1	7			7		
<b>II Main building Hall</b>									
1	Main door repair work	LS					LS		
2	Front window repair work	LS					LS		
3	Tile work for HALL Floors	Sq.mt	1	4.2	4.1		17.22		
4	Shelf work cuddapah slab 4 rows	Sq.mt	4	1.2	0.45		2.16		
5	Electrical work for 2 no's of 16 A socket and 2 switches, board wires and etc	LS					LS		
6	EB Main board cover fixing work	LS							
7	Painting work on wall & ceiling 1 coat white wash with 2 coat paint								
	a) Ceiling	Sq.mt		4.2	4.1		17.22		
	b) Walls	Sq.mt		16.6		3	49.8		
	<b>Deduction</b> a) Windows 2Nos	Sq.mt	2	1	1.2		2.4		
	b) Doors 3Nos	Sq.mt	3	1	2.1		6.3		
	<b>Total</b>						<b>58.32</b>		
8	Enamel Paint 1) 2 Windows 2Sides	Sq.mt	2	0.9	1.2		2.16		
	2) 2 Doors 2Sides		2	1	2.1		4.2		
	<b>Total</b>						6.36		
<b>III Kitchen</b>									
1	Cuddapha Self 4 row	sq.mt	4	1.2	0.45		2.16		
2	Tile work for Kitchen Floors	sq.mt	1	2.45	2.4		5.88		
3	Painting work on wall & ceiling 1 coat white wash with 2 coat paint								
	a) ceiling	sq.mt		2.45	2.4		5.88		
	b) Walls	sq.mt		9.7		3	29.1		
	<b>Deductions</b>								
	a) Door 2No	sq.mt	2	1	2.1		4.2		
	<b>Total</b>						<b>30.78</b>		
<b>Store Room</b>									
1	Shelf work cuddapah slab 4 rows	Sq.mt	4	1.5	0.45		2.7		
2	Shelf work cuddapah slab 1 rows	Sq.mt	1	2.25	0.6		1.35		
3	Painting work on wall 1 coat white wash with 2 coat paint 1) Ceiling	Sq.mt		2.4	1.5		3.6		
	2) Wall	Sq.mt		7.8		3	23.4		
	<b>Deduction</b> a) Windows 1No	Sq.mt	1	1		2.1	2.1		

		b) Door 1No	Sq.mt	1	1	1.2	1.2		
		<b>Total</b>					<b>23.7</b>		
	4	Joinery enamel painting 1) Door 1No	Sq.mt	1	1	2.1	2.1		
		2) Window 1No	Sq.mt	1	1	1.2	1.2		
		<b>Total</b>					<b>3.3</b>		
<b>IV</b>		<b>Outer side</b>							
	1	Outside wall repair works	LS				LS		
	2	Painting work on wall 1 coat white wash with 2 coat paint	sq.mt		18.8	4.65	87.42		
		<b>Deduction</b> a) Windows 3No	sq.mt	3	1	1.2	3.6		
		b) Door 1No	sq.mt	1	1	2.1	2.1		
		<b>Total</b>					<b>81.72</b>		
	3	Joinery enamel painting	sq.mt						
		a) Windows 3No	sq.mt	3	1	1.2	3.6		
		b) Door 1No	sq.mt	1	1	2.1	2.1		
		<b>Total</b>					<b>5.7</b>		
<b>V</b>		<b>Miscellaneous Expenses</b>	LS				LS		
		<b>Total</b>							